

Sheffield City Council Local Plan NES37 – Baseline Biodiversity Net Gain Assessment

Sheffield City Council

Date: 29/08/2025

Prepared by: Cura Terrae Land & Nature

Ref: 25518-NES37-BNGA-V1.0





Report to: Sheffield City Council

Report Title: Sheffield City Council Local Plan SES30 – Baseline Biodiversity Net Gain

Assessment

Version: V0.3

**Issue Date:** August 2025

Report Ref: 25518-NES37-BNGA-V1.0

Originated By:

**James Storey** 

Senior Ecologist Date: 27.08.2025

**Reviewed By:** 

**Daniel Best** 

Technical Director of Date:

Date: 28.08.2025

Ecology Approved By:

Claire Convallaria

Associate Director of Date:

**Ecology** 

ate: 28.08.2025

Prepared by:

Cura Terrae Land & Nature, 4 President Buildings, Savile Street, Sheffield, S4 7UQ. 0114 266 9292

Version	Author	Description	Date
V0.1	JS	First draft	27.08.2025
V0.2	DB	Quality assurance check 1 (QA1)	28.08.2025
V0.3	JS	Amendments following QA1	28.08.2025
VO.3	CC	QA2	28.08.2025
V1.0	AW	Client issue	04/09/2025

The report and the site assessments carried out by Cura Terrae on behalf of the client in accordance with the agreed terms of contract and/or written agreement form the agreed Services. The Services were performed by Cura Terrae with the skill and care ordinarily exercised by a reasonable Environmental Consultant at the time the Services were performed. Further, and in particular, the Services were performed by Cura Terrae taking into account the limits of the scope of works required by the client, the time scale involved and the resources, including financial and manpower resources, agreed between Cura Terrae and the client.

Other than that expressly contained in the paragraph above, Cura Terrae provides no other representation or warranty whether express or implied, in relation to the services.

This report is produced exclusively for the purposes of the client. Cura Terrae is not aware of any interest of or reliance by any party other than the client in or on the services. Unless expressly provided in writing, Cura Terrae does not authorise, consent or condone any party other than the client relying upon the services provided. Any reliance on the services or any part of the services by any party other than the client is made wholly at that party's own and sole risk and Cura Terrae disclaims any liability to such parties.

This report is based on site conditions, regulatory or other legal provisions, technology or economic conditions at the time of the Service provision. These conditions can change with time and reliance on the findings of the Services under changing conditions should be reviewed.

Cura Terrae accepts no responsibility for the accuracy of third-party data used in this report.



## **Contents**

Ex	ecutive	Summary4
1.	Intro	duction5
	1.1	Background5
	1.2	Biodiversity Net Gain Assessment
	1.3	Relevant Legislation and Policy6
2.	Meth	odology
	2.1	Background
	2.2	Biodiversity Metric Inputs
	2.3	Biodiversity Metric Baseline Calculations
	2.4	Trading Rules
	2.5	Assumptions and Limitations9
3.	Findi	ngs and Evaluation11
	3.1	Baseline Habitats11
4.	Asse	ssment and Recommendations
	4.1	Summary of Baseline Metric Calculations
	4.2	Recommendations
	4.3	BNG Principles
5.	Refe	rences
Fig	gure 1: I	Baseline Habitat Map16
Ар	pendix	1: BNG Good Practice Principles
Ар	pendix	2: BNG Policy and Legislation
Ар	pendix	3: Baseline Habitat & Hedgerow Units
Ар	pendix	4: The Statutory Biodiversity Metric Tool
Ар	pendix	5: Condition Assessment Results

## **Executive Summary**

Cura Terrae Land & Nature (Cura Terrae) was commissioned in July 2025 by Sheffield City Council (SCC) to undertake a Baseline Biodiversity Net Gain Assessment (BNGA) for a circa 30.34-hectare (ha) area of land between Creswick Avenue and Yew Lane (The Wheel), Sheffield, S35 8QN (Ordnance Survey National Grid Reference (OS NGR): SK 34452 93657), hereafter referred to as 'the Site' and as annotated in Figure 1.

At the time of writing, no detailed development proposals for the Site were available. However, it is understood that SCC may consider removing the Site from its current Green Belt designation and bringing it forward for potential residential development in the future.

Cura Terrae was also commissioned to undertake a Preliminary Ecological Appraisal (PEA) of the Site ('Sheffield City Council Local Plan NES37 – Preliminary Ecological Appraisal' Ref. 25518 V1.0 dated August 2025) (PEA, Cura Terrae 2025) along with habitat condition assessments to inform this baseline BNGA. The baseline biodiversity value of the Site has been determined using the Department for Environment, Food and Rural Affairs (DEFRA) 'Statutory Biodiversity Metric User Guide' (SBM) (DEFRA, 2024a).

For area-based habitats, the Site has a baseline biodiversity value of 85.42 Habitat Units (HU), which excludes the 16 veteran trees recorded and marked as an irreplaceable habitat (as per SBM guidance). For hedgerow habitats, the Site has a baseline biodiversity value of 43.02 Hedgerow Units (HeU). One unnamed watercourse is located on the Site (WC1, Figure 1) and within 10 m of the Site boundary further downstream. Given no River Condition Assessment (RCA) has been undertaken to date, no baseline Watercourse Units (WU) are included in the metric calculations at this stage.

It is envisaged that this baseline BNGA will form an ecological baseline to inform the Council's decision of removing the Site's current Green Belt designation. Any Biodiversity Net Gain (BNG) strategy associated with proposals for the Site should include retention of key on Site habitats and should include enhancement of habitats and new habitat creation works on Site, outline recommendations of which are included within this report. The Site habitats are considered to offer potential to support a range of species/species groups and opportunities exist to enhance habitats on Site to generate additional biodiversity value, and options such as registering the Site as a BNG site on the national register should be a consideration together with any upcoming Local Nature Recovery Strategy biodiversity priorities.

A full BNGA (feasibility and design stage) including an RCA of WC1 should be undertaken for the Site should any enhancement or development proposal be brought forward to provide a predicted quantitative biodiversity value ahead of planned works and review options to achieve 10% BNG on Site post-intervention wherever possible. A Biodiversity Gain Plan (BGP) and associated Habitat Management and Monitoring Plan (HMMP) should be produced for the Site in tandem with Biodiversity Net Gain Assessment (BNGA).



## 1. Introduction

## 1.1 Background

- 1.1.1 Cura Terrae Land & Nature (Cura Terrae) was commissioned in July 2025 by Sheffield City Council (SCC) to undertake a Baseline Biodiversity Net Gain Assessment (BNGA) for a circa 30.34-hectare (ha) area of land between Creswick Avenue and Yew Lane (The Wheel), Sheffield, S35 8QN (Ordnance Survey National Grid Reference (OS NGR): SK 34452 93657), hereafter referred to as 'the Site' and as annotated in Figure 1.
- 1.1.2 The red line boundary for the Site is taken from the 'Housing Site' boundary for NES37, as detailed in the 'Sheffield Plan Proposed Additional Site Allocations May 2025' document (SCC, 2025). At the time of writing, no detailed development proposals for the Site were available. However, it is understood that SCC may consider removing the Site from its current Green Belt designation and bringing it forward for potential residential development in the future.
- 1.1.3 Cura Terrae was also commissioned to undertake a Preliminary Ecological Appraisal (PEA) of the Site ('Sheffield City Council Local Plan NES37 Preliminary Ecological Appraisal' Ref. 25518 V1.0 dated August 2025) (PEA, Cura Terrae 2025) along with habitat condition assessments to inform this baseline BNGA. The baseline biodiversity value of the Site has been determined using the Department for Environment, Food and Rural Affairs (DEFRA) 'Statutory Biodiversity Metric User Guide' (SBM) (DEFRA, 2024a).
- 1.1.4 This report details the results of the baseline BNGA using biodiversity metric calculations based on the PEA (Cura Terrae, 2025). The methodologies employed and all survey findings are described along with an evaluation and assessment of the ecological value of the Site. Any recommendations to enhance habitats on Site to generate additional biodiversity value are also detailed where considered feasible.

## 1.2 Biodiversity Net Gain Assessment

1.2.1 Under the Environmental Act 2021, developments are required to achieve a minimum of 10% Biodiversity Net Gain (BNG) to ensure that biodiversity of the Site post development is greater than that present at baseline (pre-development) value. BNG calculations are conducted through assessing the type and condition of habitats on a site and then comparing the anticipated changes in habitat types and condition based on the development proposals. A BNGA follows the mitigation hierarchy, which sets out that everything possible must be done to firstly avoid, secondly minimise and thirdly restore/rehabilitate losses of biodiversity on Site. Only as a last resort are residual losses compensated for through biodiversity offsetting, whereby the loss of biodiversity is compensated for via new habitat creation off Site or by paying a financial sum to an offset provider. BNGA reports should adhere to the BNG good practice principles (Appendix 1).



## 1.3 Relevant Legislation and Policy

- 1.3.1 This BNGA has been compiled with reference to the following relevant nature conservation legislation, planning policy and the UK Biodiversity Framework (Appendix 2) from which the protection of sites, habitats and species is derived in England including:
  - UK Government's 25 Year Environment Plan (Defra, 2018);
  - Biodiversity 2020: A Strategy for England's Wildlife and Ecosystem Services (Defra, 2011);
  - National Planning Policy Framework (NPPF) (DLUHC, 2024);
  - The Natural Environment and Rural Communities (NERC) Act (HMSO, 2006);
  - The Environment Act (Defra, 2021); and,
  - The Local Biodiversity Action Plan (LBAP) for Sheffield originally produced by the Sheffield Biodiversity Partnership (Sheffield Biodiversity Steering Group, 'Sheffield Local Biodiversity Action Plan', 2002) with updates made in 2012 (in partnership with SCC) including production of Action Plans for four main habitat types (grassland, woodland, heathland and wetland), Action Plans for the River Don and South Yorkshire Navigation Canals, and Action Plans for Green Roofs.

## 2. Methodology

### 2.1 Background

- 2.1.1 This baseline BNGA uses the industry recognised best practice methodology within the 'Statutory Biodiversity Metric User Guide' (SBM) (DEFRA, 2024a).
- 2.1.2 The SBM uses habitat features as a measure for the value and importance to nature. The following information on each habitat are required for the metric inputs:
  - Type;
  - Area/length;
  - Distinctiveness (automatically calculated);
  - Irreplaceable habitats;
  - Condition; and,
  - Strategic significance.

## 2.2 Biodiversity Metric Inputs

#### Habitat Type and Area/Length

- 2.2.1 The Site was surveyed on 11<sup>th</sup> and 12<sup>th</sup> August 2025 by Senior Ecologist James Storey BSc MSc. The Site visit included an ecological walkover survey using the UK Habitat Classification System (UK Hab 2.0) (UKHab Ltd., 2023). The habitats present within the Site were identified and classified according to the UK Habitat Classification system which closely aligns with the SBM. The baseline habitats are displayed in Figure 1.
- 2.2.2 The SBM uses a classification system based mainly on the UKHab, with input from other systems including the Water Framework Directive (WFD) Lakes Typology (UKTAG, 2003), the European Nature Information System (EUNIS) habitat type hierarchical view (EEA, 2019), Natura 2000 Annex I habitats (JNCC, 2019) and habitats specific to the SBM.
- 2.2.3 The area/length covered by each habitat type was mapped using the QGIS 3.32.1 Geographical Information System (GIS).

#### **Habitat Condition**

2.2.4 The condition of a habitat is a measure of the biological 'working-order' of a habitat type judged against the perceived ecological optimum state for that particular habitat. The condition assessments were undertaken using the 'The Statutory Biodiversity Metric -Technical Annex 1: Condition Assessment Sheets and Methodology' spreadsheet' (DEFRA, 2024b), see Appendix 5.



- 2.2.5 Following the UKHab ecological walkover survey at the Site the condition of each habitat type was assessed and categorised as either Good, Moderate or Poor.
- 2.2.6 If a habitat type varied in condition within the Site this was recorded and mapped.

#### Habitat Strategic Significance

- 2.2.7 The SBM accounts for whether the habitat is situated in an area locally identified as significant for nature.
- 2.2.8 Data on areas and habitats locally identified as significant for nature were obtained from the following sources:
  - Multi-Agency Geographical Information for the Countryside (MAGIC) website for mapped statutory designated sites (<a href="https://magic.defra.gov.uk/magicmap.aspx">https://magic.defra.gov.uk/magicmap.aspx</a>);
  - Habitats listed within the Local Biodiversity Action Plan (LBAP) for Sheffield; and,
  - The Sheffield Loal Plan (2009).

## 2.3 Biodiversity Metric Baseline Calculations

- 2.3.1 Biodiversity metric calculations provide a numerical score for the value of existing habitats on the Site in Habitat Units (HU), Hedgerow Units (HeU) and Watercourse Units (WU), where relevant, in order for the baseline value of the Site to be quantitatively assessed.
- 2.3.2 Using the SBM, habitat values are calculated based on whether they occur commonly or whether they are rare, their area (ha) (or length (km) for linear features such as hedgerows), condition and importance within the local area, usually identified from local relevant planning policies or documents. This gives individual baseline HU, HeU and WU.
- 2.3.3 Individual trees are classified as either Urban Tree or Rural Tree, depending on the extent of urbanisation around them. The size of a tree is either Small, Medium, Large or Very Large, dependent on the diameter at breast height (centimetres). A biodiversity metric area equivalent (hectares) is automatically calculated within the SBM dependent on the tree size, however this area measurement is not included within the total habitat area (in ha) of the Site. All ancient and veteran trees are recorded individually within the biodiversity metric tool and marked as an irreplaceable habitat. This includes ancient and veteran trees in woodlands that are not themselves ancient woodlands and those in hedgerows and lines of trees.

## 2.4 Trading Rules

2.4.1 The trading rules establish minimum requirements for creating and enhancing habitats to offset specific habitat losses, ensuring no net loss. The SBM considers distinctiveness as described earlier and using this data, SBM applies trading rules that require that any habitat loss is replaced on a 'like for like' or 'like for better' basis. The trading rules are detailed below in Table 1.



Table 1: Trading Rules within the SBM

Distinctiveness Group	Trading Rules
Very High	Bespoke compensation likely to be required
High	Same habitat required
Medium	Same broad habitat or a higher distinctiveness habitat required
Low	Same distinctiveness or better habitat required
Very Low	Compensation not required

## 2.5 Assumptions and Limitations

- 2.5.1 For strategic significance, all habitats recorded at the Site have been assigned 'High strategic significance' due to either being listed as priority habitats within the Sheffield LBAP and/or being located within the Green Belt designation covered by the Sheffield Local Plan, with the exception of Urban Artificial unvegetated, unsealed surface and Urban Developed land; sealed surface which are of negligible botanical value and therefore assigned 'Low strategic significance'.
- 2.5.2 A total of 16 individual veteran trees (T11, 13-18, 20 & 25-32, Figure 1) were recorded individually within the biodiversity metric tool and marked as an irreplaceable habitat as per SBM guidance, which does not produce a baseline habitat value within the metric.
- 2.5.3 As identified in the PEA, one unnamed watercourse is located on the Site (WC1, Figure 1) and within 10 m of the Site boundary further downstream, which may be impacted by any future proposals. A River Condition Assessment (RCA) was not undertaken per the scope of works agreed between SCC and Cura Terrae, which would produce watercourse units (WU) and form part of the baseline biodiversity calculations for the Site. It has therefore been recommended that an RCA is undertaken of the above watercourse should proposals be brought forward for the Site to determine the baseline biodiversity value in WU.
- 2.5.4 It is envisaged that this baseline BNGA will form an ecological baseline to inform the council's decision of removing the Sites current Green Belt designation. Note that a full Feasibility Stage BNGA will be required, including a review of any outline recommendations made within this report alongside finalised plans for the Site where these become available.
- 2.5.5 The quantification of biodiversity is one of a number of factors to be considered when assessing the impact of the any proposed development on biodiversity. Note that this baseline BNGA does



- not cover potential impacts of any proposed development on protected species and designated sites. These are outlined within the PEA Report (Cura Terrae, 2025).
- 2.5.6 The information contained within this report is considered valid for a period of 24 months from the date of the August 2025 PEA survey visit (CIEEM, 2019). If any detailed proposals have not been brought forward by August 2027, it is recommended that the Site is re-surveyed to determine if there have been any significant changes to baseline habitats within that timeframe.

## 3. Findings and Evaluation

#### 3.1 Baseline Habitats

#### **Area-Based Habitats**

- 3.1.1 Baseline area-based habitats recorded for the Site comprised Woodland and forest Lowland mixed deciduous woodland, Woodland and forest Other broadleaved woodland, Heathland and shrub Mixed scrub, Heathland and shrub Bramble scrub, Cropland Arable field margins cultivated annually, Grassland Bracken, Grassland Modified grassland, Cropland Cereal crops, Individual trees Rural tree (including veteran trees), Urban Artificial unvegetated, unsealed surface, and Urban Developed land; sealed surface, as illustrated in Figure 1.
- 3.1.2 The total area of the Site has been calculated at 30.34 ha. The habitat type, distinctiveness, condition, area and HU of the area habitats are provided within Appendix 3. Baseline area habitats have a biodiversity value of 85.42 HU.

#### **Hedgerow Habitats**

- 3.1.3 Baseline hedgerow habitats recorded for the Site comprised Species rich native hedgerow with trees, Species-rich native hedgerow, Native hedgerow with trees, Native hedgerow, Ecologically valuable line of trees, and Non-native and ornamental hedgerow, as illustrated in Figure 1.
- 3.1.4 The total hedgerow length for the Site has been calculated at approximately 3.23 km. The hedgerow type, distinctiveness, condition and HeU are provided within Appendix 3. Baseline hedgerow habitats produced a biodiversity value of 43.02 HeU.

#### Watercourse Habitats

3.1.5 One unnamed watercourse is located on the Site (WC1, Figure 1) and within 10 m of the Site boundary further downstream. Given no RCA has been undertaken to date, no baseline Watercourse Units (WU) are included in the metric calculations at this stage.



## 4. Assessment and Recommendations

### 4.1 Summary of Baseline Metric Calculations

4.1.1 For area-based habitats, the Site has a baseline biodiversity value of 85.42 HU, which excludes the 16 veteran trees recorded and marked as an irreplaceable habitat (as per SBM guidance). For hedgerow habitats, the Site has a baseline biodiversity value of 43.02 HeU. No Watercourse Units (WU) are included in the baseline metric calculations at this stage.

#### 4.2 Recommendations

- 4.2.1 It is envisaged that this baseline BNGA will form an ecological baseline to inform the council's decision of removing the Site's current Green Belt designation. Any Biodiversity Net Gain (BNG) strategy associated with proposals for the Site should include retention of key on Site habitats and should include enhancement of habitats and new habitat creation works on Site. The Site habitats are considered to offer potential to support a range of species/species groups and opportunities exist to enhance habitats on Site to generate additional biodiversity value, and options such as registering the Site as a BNG site on the national register should be a consideration together with any upcoming Local Nature Recovery Strategy biodiversity priorities.
- 4.2.2 The following habitat retention, enhancement and compensation measures which take into account the BNG good practice principles (CIEEM, CIRIA, IEMA, 2016), and should be reviewed and verified with an appointed landscape architect if detailed proposals become available:
  - Areas of lowland mixed deciduous woodland, other broadleaved woodland, mixed scrub and bramble scrub should be retained where any future development plans would feasibly allow, with any retained areas of woodland enhanced where feasible to achieve good condition.
  - Areas of modified grassland should be retained where feasible and incorporated into any
    proposed areas of Public Open Space (POS), and enhanced to other neutral grassland to
    achieve good condition through a relaxed mowing regime to maximise biodiversity value.
  - Individual trees should be retained where feasible and additional native tree planting should be incorporated across the Site, consisting of a mixture of pollen, fruit and berry producing species. The 16 veteran trees marked as irreplaceable habitat should be retained and appropriate safeguards should be put into place to accommodate them into any future development proposals to conserve their biodiversity value.
  - The network of hedgerows and line of trees should be retained and incorporated into any
    proposed boundary treatments where feasible. Any infilling of gaps using native species
    should be considered to achieve good condition for hedgerow sections where currently in
    moderate condition, along with a continued sensitive management regime to maintain
    biodiversity value.
  - In order to satisfy the trading rules as set out in the SBM, any loss of high distinctiveness
    habitats must be compensated for with the 'same habitat required', loss of medium
    distinctiveness habitats must be compensated for with the 'same broad habitat or a higher



- distinctiveness habitat required', and loss of low distinctiveness habitats must be compensated for with 'same distinctiveness or better habitat required'. The loss of veteran trees is unacceptable as per SBM guidance, with 'bespoke compensation likely to required' should retention not be feasible.
- 4.2.3 Given that a watercourse is present on-site and within 10 m off-site, the watercourse is likely to be impacted by any future proposals, therefore it is recommended that a River Condition Assessment (RCA) is undertaken which would feed into the BNGA and any post-development scenario modelling.
- 4.2.4 A full BNGA (feasibility and design stage) should be undertaken for the Site should any enhancement or development proposal be brought forward to provide a predicted quantitative biodiversity value ahead of planned works and review options to achieve 10% BNG on Site post-intervention wherever possible. A Biodiversity Gain Plan (BGP) and associated Habitat Management and Monitoring Plan (HMMP) should be produced for the Site in tandem with Biodiversity Net Gain Assessment (BNGA).

## 4.3 BNG Principles

- 4.3.1 Appendix 1 details the BNG good practice principles (CIEEM, CIRIA, IEMA, 2016) which should be adhered to when undertaking BNG assessments in association with proposed developments. The actions within Appendix 1 should be taken into account throughout the design stage of any development at the Site should detailed proposals be brought forward.
- 4.3.2 The information contained within this report is considered valid for a period of 24 months from the date of the August 2025 PEA survey visit (CIEEM, 2019). If any detailed proposals have not been brought forward by August 2027, it is recommended that the Site is re-surveyed to determine if there have been any significant changes to baseline habitats within that timeframe.



## 5. References

- BRIG (2011). UK Biodiversity Action Plan Priority Habitat Descriptions. Available: http://jncc.defra.gov.uk/PDF/UKBAP\_PriorityHabitatDesc-Rev2011.pdf
- CIEEM (2019). Advice note on the lifespan of ecological reports and surveys. Chartered Institute of Ecology and Environmental Management, Winchester.
- CIEEM, CIRIA & IEMA (2016). Biodiversity Net Gain: Good practice principles for development.

  Available:

  <a href="https://www.iema.net/assets/newbuild/documents/IEMA%20Biodiversity%20Net%20Gain.pdf">https://www.iema.net/assets/newbuild/documents/IEMA%20Biodiversity%20Net%20Gain.pdf</a>
- Cura Terrae Land & Nature. (2025). 'Sheffield City Council Local Plan NES37 Preliminary Ecological Appraisal V1.0' ref: 25518, August 2025
- Department for Environment, Food and Rural Affairs (DEFRA) (2011). 'Biodiversity 2020: A strategy for England's wildlife and ecosystem services'. [online]. Available at: <a href="https://assets.publishing.service.gov.uk/government/uploads/system/uploads/attachment\_data/file/69446/pb13583-biodiversity-strategy-2020-111111.pdf">https://assets.publishing.service.gov.uk/government/uploads/system/uploads/attachment\_data/file/69446/pb13583-biodiversity-strategy-2020-111111.pdf</a>
- DEFRA. (2018). 'A Green Future: Our 25 Year Plan to Improve the Environment'. [online].

  Available at:

  <a href="https://assets.publishing.service.gov.uk/government/uploads/system/uploads/attachment\_data/file/693158/25-year-environment-plan.pdf">https://assets.publishing.service.gov.uk/government/uploads/system/uploads/attachment\_data/file/693158/25-year-environment-plan.pdf</a>
- DEFRA (2024a). 'The Statutory Biodiversity Metric User Guide'. Available from:

  https://assets.publishing.service.gov.uk/media/65673fee750074000d1dee31/The\_Statu
  tory\_Biodi versity\_Metric\_-\_Draft\_User\_Guide.pdf
- DEFRA (2024b). 'The Statutory Biodiversity Metric -Technical Annex 1: Condition Assessment Sheets and Methodology' (2024).
- Department for Levelling Up, Housing and Communities (DLUHC). (2024). 'National Planning Policy Framework'. [online]. Available at:

  https://www.gov.uk/government/publications/national-planning-policy-framework--2
- EEA (European Environment Agency). (2019). EUNIS Habitat Classification. Available at: https://www.eea.europa.eu/data-and-maps/data/eunis-habitat-classification.
- HMSO (2006). Natural Environment and Rural Communities Act. HMSO, Norwich. Available: https://www.legislation.gov.uk/ukpga/2006/16/pdfs/ukpga\_20060016\_en.pdf.



Joint Nature Conservation Committee (JNCC). (2019). 'Annex I Habitats List'. Available at: <a href="https://sac.jncc.gov.uk/habitat/">https://sac.jncc.gov.uk/habitat/</a>

Sheffield City Council (2011). 'Sheffield Biodiversity Action Plan'. [online]. Last accessed July 2025. Available at: https://www.sheffield.gov.uk/parks-sport-recreation/biodiversity-conservations

Sheffield City Council (2009). *'Sheffield Local Plan'*. [online]. Last accessed July 2025. Available at: <a href="https://www.sheffield.gov.uk/planning-development/sheffield-plan">https://www.sheffield.gov.uk/planning-development/sheffield-plan</a>


UKHab Ltd. (2023). 'UK Habitat Classification Version 2.0' [online]. Available at https://www.ukhab.org.

UKTAG (UK Technical Advisory Group). (2003). Guidance on Typology for Lakes for the UK. Water Directive Framework.



# Figure 1: Baseline Habitat Map





Revision	Date	Drawn by	Checked by
А	15/08/2025	JS	

Drg. Ref.: 25518.002 Scale 1

1:4,300



150 m

## Appendix 1: BNG Good Practice Principles

The BNG good practice principles are based upon issued joint guidance from the Chartered Institute for Ecology and Environmental Management (CIEEM), the Construction Industry Research and Information Association (CIRIA) and Institute for Environmental Management and Assessment (IEMA) (CIEEM, CIRIA & IEMA (2016 and CIEEM, CIRIA & IEMA 2019).

Principle	Description
1. Apply the mitigation hierarchy	Do everything possible to first avoid and then minimise impacts on biodiversity. Only as a last resort, and in agreement with external decision-makers where possible, compensate for losses that cannot be avoided. If compensating for losses within the development footprint is not possible or does not generate the most benefits for nature conservation, then offset biodiversity losses by gains elsewhere.
2. Avoid losing biodiversity that cannot be offset by gains elsewhere	Avoid negative impacts on irreplaceable biodiversity – these impacts cannot be offset to achieve No Net Loss or Net Gain.
3. Be inclusive and equitable	Engage stakeholders early, and involve them in designing, implementing, monitoring and evaluating the approach to Net Gain. Achieve Net Gain in partnership with stakeholders where possible, and share the benefits fairly among stakeholders.
4. Address risks	Mitigate difficulty, uncertainty and other risks to achieving Net Gain. Apply well-accepted ways to add contingency when calculating biodiversity losses and gains in order to account for any remaining risks, as well as to compensate for the time between the losses occurring and the gains being fully realised.
5. Make a measurable Net Gain contribution	Achieve a measurable, overall gain for biodiversity and the services ecosystems provide while directly contributing towards nature conservation priorities.
6. Achieve the best outcomes for biodiversity	<ul> <li>Achieve the best outcomes for biodiversity by using robust, credible evidence and local knowledge to make clearly-justified choices when:</li> <li>Delivering compensation that is ecologically equivalent in type, amount and condition, and that accounts for the location and timing of biodiversity losses;</li> </ul>



	<ul> <li>Compensating for losses of one type of biodiversity by providing a different type that delivers greater benefits for nature conservation;</li> <li>Achieving Net Gain locally to the development while also contributing towards nature conservation priorities at local, regional and national levels;</li> <li>Enhancing existing or creating new habitat;</li> <li>Enhancing ecological connectivity by creating more, bigger, better and joined areas for biodiversity.</li> </ul>
7. Be additional	Achieve nature conservation outcomes that demonstrably exceed existing obligations (i.e. do not deliver something that would occur anyway).
8. Create a Net Gain legacy	<ul> <li>Ensure Net Gain generates long-term benefits by:</li> <li>Engaging stakeholders and jointly agreeing practical solutions that secure Net Gain in perpetuity;</li> <li>Planning for adaptive management and securing dedicated funding for long-term management;</li> <li>Designing Net Gain for biodiversity to be resilient to external factors, especially climate change;</li> <li>Mitigating risks from other land uses;</li> <li>Avoiding displacing harmful activities from one location to another;</li> <li>Supporting local-level management of Net Gain activities.</li> </ul>
9. Optimise sustainability	Prioritise Biodiversity Net Gain and, where possible, optimise the wider environmental benefits for a sustainable society and economy.
10. Be transparent	Communicate all Net Gain activities in a transparent and timely manner, sharing the learning with all stakeholders.



## Appendix 2: BNG Policy and Legislation

#### **National**

#### **UK Government's 25 Year Environment Plan**

The UK Government's 25 Year Environment Plan (DEFRA, 2018) states a desire to 'embed a 'net environmental gain' principle for development to deliver environmental improvements locally and nationally' and plans to consult on making Biodiversity Net Gain a mandatory requirement.

On 14th March 2019, Her Majesty's Treasury confirmed that following consultation, the government will use the forthcoming Environment Bill to mandate BNG for development in England, ensuring that the delivery of much-needed infrastructure and housing is not at the expense of vital biodiversity.

#### Biodiversity 2020: A strategy for England's wildlife and Ecosystem Services

Biodiversity 2020: A strategy for England's wildlife and ecosystem services (DEFRA, 2011) is the national strategy for biodiversity. This sets out an ambition to halt the loss of biodiversity and see an increase in the area of priority habitats by 200,000 ha by 2020. Biodiversity 2020 sets in policy the objectives to improve our wildlife sites, make them bigger, develop more of them and join them up (summarised as 'Bigger, Better, More and Joined').

#### **National Planning Policy Framework**

The revised National Planning Policy Framework (NPPF) (DLUHC, 2024) refers to conserving and enhancing the natural environment. This requires Local Authorities in England to take measures to:

Conserve and enhance biodiversity;

Protect the habitats of these species from further decline;

Protect the species from the adverse effect of development; and

Refuse planning permission for development, if significant harm resulting from a development cannot be avoided, adequately mitigated, or, as a last resort, compensated for.

Although not currently a legal obligation, the NPPF refers to biodiversity and environmental net gains in the following paragraphs:

#### **Transport Infrastructure**

 Paragraph 102. "Transport issues should be considered from the earliest stages of plan-making and development proposals, so that:



d) the environmental impacts of traffic and transport infrastructure can be identified assessed and taken into account – including appropriate opportunities for avoiding and mitigating any adverse effects, and for **net environmental gains.**"

#### **Planning Decisions**

- Paragraph 120. "Planning policies and decisions should a) encourage multiple benefits from both urban and rural land ... and taking opportunities to achieve net environmental gains such as developments that would enable new habitat creation."
- Paragraph 174. "Planning policies and decisions should contribute to and enhance the natural and local environment by: ... d) minimising impacts on and providing net gains for biodiversity, including by establishing coherent ecological networks that are more resilient to current and future pressures."
- Paragraph 179. "To protect and enhance biodiversity and geodiversity plans should b) promote
  the conservation, restoration and enhancement of priority habitats, ecological networks and the
  protection and recovery of priority species; and identify and pursue opportunities for securing
  measurable net gains for biodiversity."
- Paragraph 180. "When determining planning applications, local planning authorities should apply the following principles: a) if significant harm to biodiversity resulting from a development cannot be avoided (through locating on an alternative site with less harmful impacts) adequately mitigated, or, as a last resort, compensated for, then planning permission should be refused; ... and d) ... opportunities to improve biodiversity improvements in and around developments should be integrated as part of their design, especially where this can secure measurable net gains for biodiversity."

#### **Natural Environment and Rural Countryside Act**

The Natural Environment and Rural Countryside (NERC) Act (HMSO, 2006) requires public bodies, including local authorities, 'to have regard to the conservation of biodiversity in England when carrying out their normal functions'.

#### Section 40 sets out that:

Paragraph 1. "Every public authority must, in exercising its functions, have regard, so far as is consistent with the proper exercise of those functions, to the purpose of conserving biodiversity"; and that

Paragraph 3. "Conserving biodiversity includes, in relation to a living organism or type of habitat, restoring or enhancing a population or habitat".

#### Section 41 sets out that:

Paragraph 1. "The Secretary of State must... publish a list of the living organisms and types of habitat ... of principal importance for the purpose of conserving biodiversity" based on consultation with Natural England; and that

Paragraph 3a. Every planning authority must "a) take such steps... to further the conservation of the



living organisms and types of habitat included in any list published under this section, or (b) promote the taking by others of such steps".

#### **Environment Act**

Schedule 7a of the Environment Act (HMSO, 2021) makes provision for grants of planning permission in England to be subject to a condition to secure that the biodiversity gain objective is met.

Schedule 7a Part 1 sets out that:

- (1) The biodiversity gain objective is met in relation to development for which planning permission is granted if the biodiversity value attributable to the development exceeds the pre-development biodiversity value of the onsite habitat by at least the relevant percentage.
- (2) The biodiversity value attributable to the development is the total of—
  - (a) the post-development biodiversity value of the onsite habitat,
  - (b) the biodiversity value, in relation to the development, of any registered offsite biodiversity gain allocated to the development, and
  - (c) the biodiversity value of any biodiversity credits purchased for the development.
- (3) The relevant percentage is 10%.

The Environment Act 2021 (Commencement No. 8 and Transitional Provisions) Regulations 2024 should also be consulted which includes several provisions of the Act coming into force on 12th February 2024.



# Appendix 3: Baseline Habitat & Hedgerow Units

Table A3.1: Baseline Area-based Habitats, Distinctiveness, Condition and Habitat Units

Habitat Reference	Habitat Type	Distinctiveness	Condition	Area (ha)	Habitat Units
W1	Woodland and forest – Lowland mixed deciduous woodland	High	Moderate	0.47	6.49
W2	Woodland and forest – Lowland mixed deciduous woodland	High	Poor	0.388	2.68
W3	Woodland and forest – Other broadleaved woodland	Medium	Moderate	0.06	0.55
MS1	Heathland and shrub – Mixed scrub	Medium	Moderate	0.099	0.91
BS1	Heathland and shrub – Bramble scrub	Medium	Condition Assessment N/A	0.082	0.38
BS2	Heathland and shrub – Bramble scrub	Medium	Condition Assessment N/A	0.019	0.09
FM1	Cropland – Arable field margins cultivated	Medium	Condition Assessment	0.54	2.48

Habitat Reference	Habitat Type	Distinctiveness	Condition	Area (ha)	Habitat Units
	annually		N/A		
FM2	Cropland – Arable field margins cultivated annually	Medium	Condition Assessment N/A	0.094	0.43
FM3	Cropland – Arable field margins cultivated annually	Medium	Condition Assessment N/A	0.113	0.52
B1	Grassland - Bracken	Low	Condition Assessment N/A	0.074	0.17
B1	Grassland - Bracken	Low	Condition Assessment N/A	0.035	0.08
MG1	Grassland – Modified grassland	Low	Poor	3.323	7.64
MG2	Grassland – Modified grassland	Low	Poor	4.056	9.33
MG3	Grassland – Modified grassland	Low	Poor	2.319	5.33
MG4	Grassland – Modified grassland	Low	Poor	2.09	4.81
MG5	Grassland – Modified grassland	Low	Poor	2.59	5.96



Habitat Reference	Habitat Type	Distinctiveness	Condition	Area (ha)	Habitat Units
MG6	Grassland – Modified grassland	Low	Poor	4.57	10.51
MG7	Grassland – Modified grassland	Low	Poor	0.039	0.09
C1	Cropland – Cereal crops	Low	Condition Assessment N/A	5.356	12.32
C1	Cropland – Cereal crops	Low	Condition Assessment N/A	1.732	3.98
C1	Cropland – Cereal crops	Low	Condition Assessment N/A	1.798	4.14
U1	Urban – Artificial unvegetated, unsealed surface	Very low	Condition Assessment N/A	0.359	0.00
U2	Urban – Developed land; sealed surface	Very low	Condition Assessment N/A	0.129	0.00
T2 <sup>1</sup>	Individual trees – Rural tree	Medium	Moderate	0.008	0.07



<sup>&</sup>lt;sup>1</sup> Small sized individual tree in moderate condition

Habitat Reference	Habitat Type	Distinctiveness	Condition	Area (ha)	Habitat Units
T3, 5-7, 33-36 & 37 <sup>2</sup>	Individual trees – Rural tree	Medium	Moderate	0.146	1.35
T8 <sup>3</sup>	Individual trees – Rural tree	Medium	Good	0.016	0.22
T19 <sup>4</sup>	Individual trees – Rural trees	Medium	Moderate	0.036	0.34
T4, 9-10, 12, 21-24 & 38 <sup>5</sup>	Individual trees – Rural trees	Medium	Good	0.329	4.55
T11, 13- 18, 20 & 25-32 <sup>6</sup>	Individual trees – Rural trees	Medium	Good	1.223	0.007
Total Habita	at Units (HU)				85.42

Table A3.2: Baseline Hedgerow Habitats, Distinctiveness, Condition and Hedgerow Units

Habitat Type	Distinctiveness	Condition	Length (km)	Hedgerow Units
H1 – Non-native and	Very low	Poor	0.082	0.09

 $<sup>^{\</sup>rm 2}\,{\rm Medium}$  sized individual trees in moderate condition



<sup>&</sup>lt;sup>3</sup> Medium sized individual trees in good condition

<sup>&</sup>lt;sup>4</sup> Large sized individual tree in moderate condition

<sup>&</sup>lt;sup>5</sup> Large sized individual trees in good condition

 $<sup>^{\</sup>rm 6}$  Very large sized veteran trees in good condition

<sup>&</sup>lt;sup>7</sup> Irreplaceable habitat – no units generated

Habitat Type	Distinctiveness	Condition	Length (km)	Hedgerow Units
ornamental hedgerow				
H2 – Non-native and ornamental hedgerow	Very low	Poor	0.019	0.02
H3 – Native hedgerow with trees	Medium	Good	0.04	0.55
H4 – Species-rich native hedgerow with trees	High	Good	0.135	2.79
H5 – Native hedgerow	Low	Good	0.096	0.66
H6 – Species-rich native hedgerow with trees	High	Good	0.049	1.01
H7 – Species-rich native hedgerow	Medium	Good	0.146	2.01
H8 – Non-native and ornamental hedgerow	Very Low	Poor	0.127	0.15
H9 – Native hedgerow	Low	Good	0.078	0.54
H10 – Non-native and ornamental hedgerow	Very low	Poor	0.041	0.05
H11 – Non-native and ornamental hedgerow	Very low	Poor	0.021	0.02
H12 – Species-rich native hedgerow with trees	High	Good	0.21	4.35



Habitat Type	Distinctiveness	Condition	Length (km)	Hedgerow Units
H13 – Native hedgerow with trees	Medium	Good	0.118	1.63
H14 – Species-rich native hedgerow	Medium	Good	0.168	2.32
H15 – Native hedgerow	Low	Good	0.086	0.59
H16 – Species-rich hedgerow with trees	High	Good	0.099	2.05
H17 - Species-rich hedgerow with trees	High	Good	0.171	3.54
H18 – Species-rich native hedgerow with trees	High	Good	0.054	1.12
H19 – Native hedgerow	Low	Good	0.287	1.98
H20 – Native hedgerow	Low	Good	0.113	0.78
H21 – Native hedgerow	Low	Moderate	0.033	0.15
H22 – Native hedgerow	Low	Good	0.106	0.73
H23 - Species-rich native hedgerow with trees	High	Good	0.141	2.92
H24 - Species-rich native hedgerow with trees	High	Good	0.112	2.32
H25 - Species-rich native	High	Good	0.12	2.48



Habitat Type	Distinctiveness	Condition	Length (km)	Hedgerow Units
hedgerow with trees				
H26 - Species-rich native hedgerow with trees	High	Moderate	0.224	3.09
H27 – Species-rich native hedgerow	Medium	Moderate	0.056	0.52
H28 – Species-rich native hedgerow	Medium	Good	0.024	0.33
H29 – Species-rich native hedgerow	Medum	Good	0.127	1.75
H30 – Species-rich native hedgerow with trees	High	Good	0.067	1.39
H31 – Species-rich native hedgerow	Medium	Good	0.03	0.41
L1 – Ecologically valuable line of trees	Medium	Good	0.048	0.66
Total Hedgerow Units (HeU)				43.02

# Appendix 4: The Statutory Biodiversity Metric Tool

Provided as a separate Microsoft Excel Spreadsheet.



## **Appendix 5: Condition Assessment Results**

Provided as a separate Microsoft Excel Spreadsheet.

